

Lake Michigan “Riprap” Projects


Reed Gaedtke – Manitowoc County Code Administrator

Kathi Kramasz – DNR Waterway and Wetland Specialist

A kayaker wearing a blue wetsuit and a red helmet is paddling through white-water rapids. The water is turbulent with large, frothy waves. The kayaker is positioned in the middle ground, facing away from the camera and slightly to the right. The background shows more rapids and the continuation of the river.

Three different DNR applications/projects

1. McHugh North – 300'
2. McHugh South – 600'
3. Mansukhani - 750'

A scenic view of a lake with a rocky shoreline and a dense forest in the background. The water is blue with gentle ripples. The shoreline is composed of light-colored, irregularly shaped rocks. Behind the rocks is a lush green forest with various trees and shrubs. A wooden fence is visible in the background on the left side.

Three ways DNR can approve Shore Protection Projects

1. Exemption
2. General Permit
3. Individual Permit




PARCEL# 01701101300700
PROPERTY NORTH OF
16929 LAKESHORE RD
TWO RIVERS, WI. 54241
SITE PLAN

300'

RIP RAP


RIP RAP



A photograph of a riverbank. The foreground is filled with greenish-blue water. The middle ground shows a sandy and rocky shoreline with some fallen branches. Behind the shoreline is a steep, eroded bank of reddish-brown soil. The top of the bank is covered with dense green trees and shrubs. A horizontal yellow line is drawn across the image, just above the water level, indicating the Ordinary High Water Mark (OHWM).

First Step Determining Jurisdiction


1. DNR regulates from OHWM waterward
2. County regulates from OHWM landward

A photograph showing a chain-link fence running along a rocky shoreline. The fence is supported by several dark metal posts. To the left of the fence, there are large, light-colored rocks and some sparse vegetation. To the right, the ground is covered with dry, brown leaves and some green grass. In the background, a body of water is visible, and a small sign on a post near the water reads "No Trespassing".

Set OHWM at
neighboring property







**BLUFF REMEDIATION AND
SHORE PROTECTION
IMPROVEMENTS**

SHEET NAME:
**BLUFF AND SHORE TOPOGRAPHY AND
NEAR SHORE BATHYMETRY**

PLAN DATE:
 1/15/2024

TAMCOR, LTD.
 740 WATERS EDGE ROAD
 RACINE, WISCONSIN 53402
 www.tamcorconsulting.com
 PHONE: 847-404-1868


PROJECT NO.
 23925

SHEET 3 OF 11



| | | | |
|------------------------------------|---|---------------------------------|---|
| <u>Date:</u> | July 18, 2023 | | |
| <u>Owner:</u> | John McHugh 16929 Lakeshore Rd Two Rivers, WI. 54241 | <u>Project Location:</u> | Parcel# 01701101300700 North of 16929 Lakeshore Rd. Two Rivers, WI. 54241 |
| <u>Project description:</u> | What: Rip rap, Purpose: Prevent erosion Need: bank being eroded. | | |
| <u>Description of work:</u> | Shoreline restoration. PWS will start by removing any fallen trees on northern parcel. Once the bluff face is cleaned off PWS will lay fabric against bluff, dig a 3ft trench at toe of slope and start placing stone. Stone to be placed at an average of 6' high at a 2:1 slope and will follow the natural contour of the shoreline. The total length of Riprap placed to be 300'. | | |
| <u>Timeline:</u> | <p>Start date: We have this project tentatively scheduled for December 4th, 2023. However, we may have to start earlier or later due to the weather or other unforeseen circumstances. Also, we are willing to shift dates to comply with any work blackout dates the WI. DNR needs.</p> <p>Sequence of work: Day 1 – Inspect equipment for fluid leaks. Drop off equipment and brief job with crew. Start to remove fallen trees. Day 2 continue removing fallen trees and line the bank with geo-textile fabric. Day 3-66 finish laying fabric, dig trench to key toe stone of rip rap, lay rip rap. Day 67 (last day) ensure all material is accounted for, no contamination of area, at our facility inspect and remove aquatic plants, animals, and mud from equipment, drain all water from equipment, wash all equipment with high pressure water and other WI DNR BMP's</p> <p>End date: We have this project tentatively scheduled to end on March 7th, 2024. However, this day may change due to pace of work, weather, or other unforeseen circumstances.</p> | | |
| <u>Materials:</u> | <p>All stone will be natural stone obtained from a local quarry and it will be irregular in size and shape.</p> <p>Geo-Textile fabric – As needed.</p> <p>24" - 36" Rip rap – 1000 ton</p> <p>12" - 18" Rip rap – 100 ton</p> | | |

580






1. Purpose of revetment to absorb energy with spaces between large rocks

2. Rocks still have flat faces so some energy moves up the slope of the revetment

3. Splash pad is constructed for extreme wave conditions so that water does not come over the armor stone and erode the bank behind the revetment

4. This could collapse the entire structure

What is a splash pad?



Splashpads should only be allowed in unique limited situations on the Great Lakes where an engineering analysis shows that it is needed to maintain the integrity of the revetment/slope

DNR Review of a Revetment Project

A photograph of a large, powerful wave crashing against a rocky shoreline. The water is white with foam, and the sky is overcast and grey. In the background, there are trees with some autumn-colored foliage.

- Will the project have an impact on fisheries, wildlife, natural scenic beauty, water quality, etc?
- Has the applicant provided enough information to show that the revetment will not fail and cause environmental degradation?
- Will the project impact neighboring properties?
- All revetments change the near shore area, what is the cost/benefit to the landowner vs environmental change?
- Equipment operating below the OHWM

Lakebed downcutting example





Less than 60 days

ANT: READ CAREFULLY

PROJECT GROUND-DISTURBING ACTIVITIES AND DNR PERMITTING: as the project footprint overlies and/or is immediately proximal to historic structures as well) the applicant:

DO NOT consult with the Wisconsin Historical Society (WHS) (Contact: Compliance WHS compliance@wisconsinhistory.org) before proceeding with CRM firm to facilitate same) - conduct archaeological investigations and/or monitoring, as required by WHS (cf. attached form). Include


DO NOT forward one (1) copy original (digital) of all materials submitted to WHS to DNR (including report of archaeological investigations, 1027 W. St. Paul Ave, Milwaukee, WI 53233, Richard.kubicek@wisconsin.gov ... these materials *must* include a copy of a USGS topographic map of the project footprint(s)

if project includes non-burial components and/or sites, those components/sites *must* also be investigated/reported or the report of investigations (ROI) *must* include WHPD map (as attached below) with the project footprint delineated thereon or the project will not be cleared

DO NOT forward to DNR written "burial site project clearance" documentation from the WHS before the permit application will be cleared referencing the burial site and other project related archaeological site numbers [as indicated]).


Information should be copied *exactly* and provided to the applicant, along with attached map – INCLUDING the archaeological site numbers (correspondence).

PROVIDE the attached "Request to Disturb a Human Burial Site" form






Nature's Beauty



Original plan




Vegetated shoreline






Low bluff, shallow slopes






Splash pad 40' wide




Original plan

Splash pad 4' high and 35' wide









Revised plan

PLAN DATE:
1/15/2024

TAMCOR, LTD.

PROJECT N

Enkamat®

General Installation for Slopes and Channels Used for Enkamat 7000, 7200, 7900 Series

These suggestions represent generally accepted procedures for successful installation of Enkamat. These instructions may be followed, modified, or rejected by the owner, engineer, contractor or their representative since they, not Colbond, Inc. are responsible for planning and executing procedures appropriate to a specific application.

Enkamat is packaged in rolls that are easy to ship, store and install. No heavy equipment is needed for installation of matting: a roll can be handled by one or two workers.


- 1. Site Preparation:** Whether slope or channel, the site must be shaped to the design specifications (grade, geometry, density of soil, etc.) and then dressed to be free of soil clods, clumps, rocks, or vehicle imprints of any significant size that would prevent the Enkamat from lying flush to surface contours.
- 2. Anchor Trench:** Anchor trenches are required to securely fasten the Enkamat to the ground surface. In channel applications, the initial anchor trench is installed at the beginning of the channel and intermediate check slots are spaced at approximately 25 feet* intervals downstream depending on flow conditions and whether you soil fill or not. The Enkamat is installed into the bottom of the trench and fastened with pins spaced 3 feet apart. The anchor trench / intermediate check slots are then backfilled and compacted in a manner as to not damage the Enkamat.

* In lieu of excavated check slots, a double row of pins (one a number 1 or 2 rebar pinned across the mat) may be used at 25-foot intervals.

- 3. Enkamat Installation:** Roll the Enkamat down the slope or channel. The overlap between rolls is 3 to 4 inches. The splice between rolls is between 2 and 3 feet. Shingle the roll in the direction of water flow. Install pins down the center of each mat (mat is 3.25 feet wide) staggering them between the outside pins with a spacing interval of 3 to 5 feet. Pins patterns will vary depending upon application, soil type, slope or channel slope, geometry, etc. A rule of thumb for estimating the amount of pins required for a project is:

1:1 to 2:1 slopes
3-4 pins per sq. yd.

3:1 and lesser slopes
2-3 pins per sq. yd.



| | | |
|---------------------------------|---|---|
| Description | Enkamat 7010 is a 3-dimensional turf reinforcement mat (TRM) made of continuous monofilament fibers fused at their intersections. 98% percent of the Enkamat is open and available for soil, much and root interlock, creating the most effective soil reinforcement mat (RSM) available. Enkamat is manufactured from nylon 6. | eliminate the buoyancy factor associated with submerged conditions. It provides permanent flrst protection in vegetated channels, as well as on slopes. |
| Recommended Applications | <ul style="list-style-type: none"> Permanent erosion control for vegetated channels with expected shear stresses ≤ 8.8 psf Permanent erosion control for moderate to steep slopes ≤ 33.8 ft/s Support and enhance performance of ecosystem plants Substrate for hydrologically applied Reelac Growth Medium (RGM) or Banded River Acacia (BRA) Meets requirements of DOTA 1993 Type III TRM Material Specific Gravity of > 1.14 prevents buoyancy—the No Float TRM | |

Technical Data

Mechanical Properties

| | Test Method | Units | MAK® Test Value |
|------------------|-------------|--|-----------------|
| Tensile Strength | ASTM D 6818 | lb/in (ksi) | 1.8 (125) |
| Thickness | ASTM D 6325 | mm (in) | 4.25 (0.25) |
| Mass/Unit Area | ASTM D 6566 | g/m ² (oz/yd ²) | 150 (4.5) |
| Resiliency | ASTM D 6524 | % | ≥ 80 |
| UV Stability | ASTM D 4355 | % strength retained | 80 @ 2000 hr |

Performance Properties

| | Test Method | Units | Typical Test Value |
|---------------------------------|----------------------|-----------|---------------------------|
| Permissible Velocity | 45 minute, vegetated | Rune test | m/s (ft/s) |
| | 30 hour, vegetated | Rune test | m/s (ft/s) |
| Permissible Shear Stress | 45 minute, vegetated | Rune test | MMN (lb/ft ²) |
| | 30 hour, vegetated | Rune test | MMN (lb/ft ²) |
| Manning's "n" Range | Rune test | | 0.059—0.067 |

Packaging

| Property | Units | Nominal Value |
|-------------------------|------------------------|------------------------|
| Roll Dimensions (w x l) | m (ft) | 2.4 x 31.4 (8.0 x 100) |
| Roll Area | m ² (sq ft) | 75.4 (815) |
| Estimated Roll Diameter | m (in) | 0.41-0.71 (16-28) |
| Estimated Roll Weight | kg (lb) | 34 (75) |
| Color | | Black |

To the best of our knowledge, the information contained herein is accurate. However, Low & Bonar Inc. cannot assume any liability whatsoever for the accuracy or completeness thereof. Final determination of the applicability of this information is subject to the user's interpretation of the nature of use and whether the suggested use infringes any patents. It is the responsibility of the user. These products may be treated by persons or products pending.



Low & Bonar Inc.
PO Box 1667 / 8140 / MC 26708
1-800-565-7391 / 1-800-565-5009
www.enkamat.com / info@lowbonar.com

© 2017 Low & Bonar Inc. All rights reserved.

BLUFF PLANTING DIRECTIONS:

- 1.) SCARIFY FINISH-GRADED BLUFF SURFACES
- 2.) INSTALL TURF REINFORCEMENT MATTING PER ABOVE INSTRUCTIONS
- 3.) PLACE ±3" ORGANIC LOAM/COMPOST BLEND
- 4.) SOW NATIVE BLUFF SEED MIXES PER SUPPLIERS RECOMMENDATIONS
- 5.) PLACE AND STAKE STRAW EROSION BLANKETS ACROSS ALL SEEDED SURFACES
- 6.) IRRIGATE AS NEEDED

BLUFF BANK AND NEARSHORE GEOLOGY

BLUFF: 600.0 TO 574.0 HAVEN & TWO RIVERS TILL LEAN CLAY, STIFF TO VERY STIFF PER WISCONSIN SHORELINE INVENTORY & OBLIQUE VIEWER AT SECTIONS 30-4 AND 30-5b, JUST NORTH AND SOUTH OF SUBJECT SITE. DATA CONFIRMED BY ONSITE SOIL BORINGS.

LAKESHORE ROAD

±75x±86' STAGING AND STOCKPILE AREA

60' min. FRONT YARD SETBACK

60' min. FRONT YARD SETBACK

LOT 3

±86'

±75'

25' min. SIDE YARD SETBACK

25' min. SIDE YARD SETBACK

LOT 2

SITE BENCHMARK BM101
mag in ppl
BM101
602.28

75' min. REAR YARD SETBACK

House
Garage
Patio
Deck

Asphalt Driveway

25' min. SIDE YARD SETBACK
SITE BENCHMARK BM100
mag in tree
BM100
600.54

25' min. SIDE YARD SETBACK

TEMPORARY CONSTRUCTION ACCESS ROAD
8" CRUSHED GRAVEL OVER GEOTEXTILE FABRIC

TEMPORARY CONSTRUCTION FENCE/
EROSION CONTROL SILT FENCING

75' min. REAR YARD SETBACK

75' min. REAR YARD SETBACK

75' min. REAR YARD SETBACK

EXISTING ISLAND

PERMIT APPLICATION PENDING

PREVIOUS PERMIT

SOUTH PROPERTY LINE

25' min. SIDE YARD SETBACK

SECTION A
SECTION B
SECTION C
SECTION D
SECTION E
SECTION F
SECTION G
SECTION H
SECTION I
SECTION J
SECTION K
SECTION L
SECTION M
SECTION N


A permit is issued for each parcel of land



Floodplain Permit

Digging was going to occur at the toe of the slope and beach area which is classified as floodplain. Therefore a permit to perform work in a floodplain was issued

All spoils must be removed from the floodplain area and deposited upland or offsite.




Shoreland Permit

The shoreland permit covered the filling and grading done on each parcel because of the amount of area being disturbed and the steepness of the slope.

An erosion control plan was submitted which included the construction of silt fencing and other erosion control measures and also replanting of vegetation; the removal of the temporary access drive to the lakeshore; and placement of any splashguard or other project items approved by the DNR process.





Mansukhani Project

5.72 ac.

1.353.05

T21N R24E
S11 SE-SE

16704

LAKESHORE RD

133.49

059

01701401600100
6.72 ac.

16633

435.41

01400100000
480 ac

T21N R24E
S14 NE-NE

0000




NOTE:
PLACE SILT FENCE ON TABLELAND AND
EROSION CONTROL ROLL ON SLOPES

SITE BENCHMARK:
TOP OF WELL HEAD.
ELEV.=611.21 IGLD85

EXISTING TREE LINE
TO BE PROTECTED

TREE
PROTECTION
FENCING

LIMITS OF BLUFF CUT




DISPOSAL AREA FOR CLAY
BLUFF CUT AND REVETMENT
TOE TRENCH CLAY.
CONFIGURATION AND GRADES
PER OWNER. WHEN
COMPLETED, AREA TO BE
SEEDED AND COVERED WITH
EROSION MAT.

PLACE SILT
FENCE ALONG
NORTH SIDE
CONSTRUCTION
ROAD

EXISTING TREE LINE
TO BE
PROTECTED

STAGING AREA
±100'x±60'



LAKE MICHIGAN

LAKE LEVEL=579.0 IGLD85 (3-22-2024)
(NAVD88-0.45' = IGLD85)

SHEET 6
ING AND
CONTROL
AREA

REVTMENT PER
CROSS SECTIONS
AND DETAILS ON
SHEETS 8
THROUGH 12

SPLASHSTONE PER
CROSS SECTIONS
AND DETAILS ON
SHEETS 8
THROUGH 12

| | | | | | |
|--------------------------------|---|--|---|-------------------------|---|
| REVISION General General | LOCATION: 16633 LAKESHORE ROAD TOWN OF TWO CREEKS, WI | PROJECT: BLUFF REMEDIATION AND SHORE PROTECTION IMPROVEMENTS | SHEET NAME: PROPOSED CONDITIONS SHORE AND BLUFF IMPROVEMENT PLAN, TEMP. CONSTRUCTION ROAD ACCESS, STAGING AREA AND EROSION CONTROL. | PLAN DATE: 9/15/2022 | TAMCOR, LTD. 740 WATERS EDGE ROAD RACINE, WISCONSIN 53402 www.tamcorconsulting.com PHONE: 847-404-1868 |
|--------------------------------|---|--|---|-------------------------|---|







2018





2020








Bluff cut >35'

Revetment 10' high



Revetment width 20'+

| | | | | |
|---|----|----------|---|--|
| | | | LOCATION: 16633 LAKESHORE ROAD TOWN OF TWO CREEKS, WI | PROJECT: BLUFF REMEDIATION AND SHORE PROTECTION IMPROVEMENTS |
| 4 | ck | General | | |
| 4 | ck | General | | |
| | BY | REVISION | | |





DISPOSAL AREA FOR CLAY BLUFF CUT AND REVETMENT TOE TRENCH CLAY. CONFIGURATION AND GRADES PER OWNER. WHEN COMPLETED, AREA TO BE SEEDED AND COVERED WITH EROSION MAT.


FENCE ALONG NORTH SIDE OF CONSTRUCTION ROAD

EXISTING TREE LINE TO BE PROTECTED

STAGING AREA
±100'x±60'

Land disturbance in shoreland zone of creek and Lake Michigan

CONSTRUCTION ACCESS ROAD TO/FROM LAKE SHORE ROAD (SEE AERIAL VIEW ON SHT 3 FOR CONTINUATION)





2024



1. Create work zone in yard area

Work above OHWM

2. Grade top of bank back





3. Topsoil stockpile at top of bluff



4. Create access road





Revetment Process

Dig the trench

Place fabric

Place filter stone

Place armor stone





Site stabilization above OHWM done after spring rains



Finalize site restoration

McHugh Project

- Excellent near shore resources above and below OHWM
- Minimal bank grading
- Minimal tree cutting/veg disturbance above OHWM
- No splash pad
- Large rock around 36" diameter

Mansukhani Project

- No buffer present since at least the 1970's
- Significant bank grading on slope
- Significant shoreland disturbance above top of bluff
- Splash pad
- Large rock from 36" up to 72" diameter
- Additional creek bank work needed



This is NOT a
Public Beach
No Trespassing
No Exceptions

Swanton (2015) 40 (2015) 101-102 101-102
101-102 Chapter 101-102

